

**Atacama
Large
Millimeter
Array**

Back End Subsystem (including Correlator)

R. Kurz

ESO-Wide Review
13-17 February 2003



ALMA Project

Back End IPT / Main Tasks

- Intermediate Frequency (IF) Processing
 - Down convert IF from front-end receivers
 - Digitization (Digitizer, Demux, Test Bench)
 - Sampler clock
 - IF Data Transmission System (Digital & Fiber Optic)
- Timing, Synchronization, LO Distribution
 - LO Reference including 2nd LO (1st LO in Front-ends)
 - Reference generator & distributor (10, 25, 125 MHz, 48 ms)
 - 2nd LO Synthesizer
- Photonic Local Oscillator (1st LO) Reference (100 GHz)
 - Laser synthesizer
 - Line length corrector
 - LO reference receiver



ALMA Project


Backend IPT/Share of Tasks

- IFDC Prototype and Production North America
- Digitizer Prototype and Production Europe
- Sampler Clock Production Europe
- IF Data Transmission System
Prototype and Production NA, Europe (FOX,
FOR, WDM, Fiber)
- LO Prototype and Production NA, Europe (H-maser,
Photomixer, Optical
Comb Generator - OCG)
- Integration support will follow the above NA/Europe scheme



ALMA Project

European Back End Team Organization





ALMA Project

Backend Status



- Digitizer/ Demux
 - 3 generations of ASIC digitizer design and production in cooperation with STMicroelectronics R&D
 - 2 demultiplexer designs (SiGe and GaAs ASICs plus FPGAs)
- IF Data Transmission
 - Fiber optic system design and benchtop demonstration of 120 Gbps link
- Photonic LO
 - Design and production of 100 GHz waveguide-mounted photomixer
 - Design and demonstration of 390 GHz photomixer
- Apr 2002 - Back End Subsystem PDR



ALMA Project

ALMA Digitizer/Sampler


Response to 3 GHz input; clock @ 4 GHz





Fiber Optic Data Transmission

Data Transmission System





ALMA Project

Back End Phase 2 Work Plan

- Digitizer/Demux
 - Contract with STM for ASIC digitizer final development foundry run, accelerated life test, and device production
 - Produce and test 2 types of demux ASICs
 - Deliver prototype digitizer/demux for Test Interferometer (TI) by end of 2003
 - Deliver 8 pre-production units in 2004-2005
- Sampler Clock
 - Deliver existing IRAM clock for TI by end of 2003
 - Deliver 8 pre-production units in 2004-2005



ALMA Project

Back End Phase 2 Work Plan

- IF Data Transmission
 - Deliver 2 prototype assemblies for TI by end of 2003
 - Deliver 8 pre-production units in 2004-2005
- Photonic LO
 - Complete development of 100 GHz photomixer
 - Two sources of photomixer chips
 - Deliver 8 pre-production photomixers
 - Complete development of OCG (noise, stability, tuning)
 - Deliver 1 pre-production OCG



ALMA Project

Correlator Status and Plan

- Baseline (1st generation) correlator is North American task
 - Prototype baseline correlator nearly completed
- 2nd generation correlator is European task
 - Feasibility study and preliminary design studies completed in cooperation with Japan
 - Only preliminary design planned in Phase 2
 - Detailed design and prototyping will be included in FP6 proposal for ALMA infrastructure construction